



LEGEND

- KERBS TO BE REMOVED AND TAKING TO TIP OFF SITE.
 - EDGING TO BE REMOVED AND TAKING TO TIP OFF SITE.
 - HALF BATTER KERB TO BE LAID AS PER STD DRG.11106.
 - FLAT TOP EDGING TO BE LAID AS PER STD DRG.11202.
 - DROPPED PEDESTRIAN CROSSING AS PER STD DRG.11313A.
 - FOOTWAY SURFACING AS PER CROSS SECTIONS.
 - UNUSED GRASS AREA.
- STREET FURNITURE
- SP SIGN POLE TO BE RELOCATED.
 - SP SIGN POLE TO REMAIN.
 - LC LIGHT COLUMN TO BE RELOCATED.
 - LC LIGHT COLUMN TO REMAIN.
 - G REMOVE EXISTING GULLY.
 - Pr.G INSTALL NEW GULLY AS PER STD DRG 5601.3 TO SUIT NEW KERB LINE.
 - MH MANHOLE TO BE ADJUSTED TO NEW LEVELS.
 - BT POLE.
 - BT PROPERTY DEVELOPMENT SIGN TO BE RELOCATED.
 - OVERHEAD BT CABLE
- NOTES:
- MINIMUM FOOTWAY WIDTH - 3m

REVISION	DETAILS	BY	DATE

East Lothian Council
Partnership and Community Services
Road Services
John Muir House
Haddington
East Lothian
Tel: 01620 82927



A1087 DUNBAR TO BROXBURN
EH42 1LN
FOOTWAY CONSTRUCTION
PROPOSED DETAILS ONE

Date: FEB 2020
Scale: AS STATED
Client: N/A

Drawn by: R.MAN
Checked by: GOWCR

DRG. NO. EL20769250-01